

~~B-1572~~ B-1572
484

MAG-1#041572904

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM
for the
NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

SEE INSTRUCTIONS

1. NAME				
COMMON: 1212 St. Paul St.				
AND/OR HISTORIC:				
2. LOCATION				
STREET AND NUMBER: 1212 St. Paul Street				
CITY OR TOWN: Baltimore				
STATE: Maryland		COUNTY:		
3. CLASSIFICATION				
CATEGORY (Check One)		OWNERSHIP		STATUS
<input type="checkbox"/> District <input checked="" type="checkbox"/> Building <input type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object		<input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both		<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
		Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered		ACCESSIBLE TO THE PUBLIC Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No
PRESENT USE (Check One or More as Appropriate)				
<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input checked="" type="checkbox"/> Private Residence	<input type="checkbox"/> Other (Specify)	
<input type="checkbox"/> Educational	<input type="checkbox"/> Military	<input type="checkbox"/> Religious		
<input type="checkbox"/> Entertainment	<input type="checkbox"/> Museum	<input type="checkbox"/> Scientific		
4. OWNER OF PROPERTY				
OWNER'S NAME: George Fisher				
STREET AND NUMBER: 5807 Dale Road				
CITY OR TOWN: Baltimore		STATE: Maryland		21209
5. LOCATION OF LEGAL DESCRIPTION				
COURTHOUSE, REGISTRY OF DEEDS, ETC.: Records Office, Room 601				
STREET AND NUMBER: Baltimore City Courthouse				
CITY OR TOWN: Baltimore		STATE: Maryland		21202
Title Reference of Current Deed (Book & Pg. #): RHB 2696-207				
6. REPRESENTATION IN EXISTING SURVEYS				
TITLE OF SURVEY: City of Baltimore Neighborhood Survey				
DATE OF SURVEY: 1975 <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input checked="" type="checkbox"/> Local				
DEPOSITORY FOR SURVEY RECORDS: Commission for Hist. and Arch. Pres.				
STREET AND NUMBER: Room 900 26 S. Calvert St.				
CITY OR TOWN: Baltimore		STATE: Maryland		21202

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input type="checkbox"/> Altered	<input checked="" type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		
DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE						
<p>This brick house which is located near the middle of the block is $3\frac{1}{2}$ stories high and 3 bays wide, and was built around 1873. It is laid in running bond. The doorway, framed in marble, has a basket handle arch and has a transom. Five steps lead to a stoop before a vestibule and inner door. All the windows except the attic are rectangular, one over one lights with flat-arched brick lintels and marble sills. The Mansard roof, rising above a projecting cornice which is supported by brackets, is pierced by two full-arched dormer windows, the surrounds of which appear to be wood.</p> <p>Above the third story windows are recessed brick features which are purely decorative, adding interest to an otherwise plain area.</p> <p>The attic has a pavillion treatment similar to the other houses in this group. The dormer windows are double hung with 2/2 lights. The marble ashlar base is punctured by a sunken entranceway and a window, and is capped by a projecting marble belt course. The tall first floor windows rise to the height of the main entrance opening.</p>						

SEE INSTRUCTIONS

B. SIGNIFICANCE**PERIOD (Check One or More as Appropriate)**

- | | | | |
|--|---------------------------------------|--|---------------------------------------|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input type="checkbox"/> 18th Century | <input type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input checked="" type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known)**AREAS OF SIGNIFICANCE (Check One or More as Appropriate)**

- | | | | |
|--|---------------------------------------|---|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Phi- | <input type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | losophy | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Science | _____ |
| <input checked="" type="checkbox"/> Architecture | <input type="checkbox"/> Landscape | <input type="checkbox"/> Sculpture | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Architecture | <input checked="" type="checkbox"/> Social/Human- | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Literature | itarian | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Military | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Conservation | <input type="checkbox"/> Music | <input type="checkbox"/> Transportation | _____ |

STATEMENT OF SIGNIFICANCE

See 1200 St. Paul St.

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY				OR	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES				
CORNER	LATITUDE				LONGITUDE				
	Degrees	Minutes	Seconds		Degrees	Minutes	Seconds		
NW	0	'	"	0	'	"	0	'	"
NE	0	'	"	0	'	"	0	'	"
SE	0	'	"	0	'	"	0	'	"
SW	0	'	"	0	'	"	0	'	"

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification: 20' by 102'

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE: MARSHA ROZANSKY, PLANNING ASSISTANT
~~Mrs. Cleora Thompson, Neighborhood Survey Coordinator~~ORGANIZATION
Commission for Hist. and Arch. Pres.DATE
Oct. 1975STREET AND NUMBER:
Room 900 26 S. Calvert St.CITY OR TOWN:
BaltimoreSTATE
Maryland

21202

12. State Liaison Officer Review: (Office Use Only)


Significance of this property is:

National ☐ State ☐ Local ☐

Signature

REVISIONS.

LOTS 34 & 35 CONSD PER App 2175 C. SH. 3136.
 LOT 21/22 PER App 2141 8125.
 LOT 25/29 CONSD PER App C SH 3600.
 LOTS 17/20 CONSD PER App C SH 3627.



NOTICE

THIS IS A REAL PROPERTY PLAT AS PROVIDED FOR UNDER ARTICLE 71.1 OF THE CITY CHARTER. IT IS CONTROLLED BY THE BOARD OF SURVEYS AND MAPS AND IS NOT TO BE USED FOR ANY OTHER PURPOSE.

TRACED BY *Moorehead*
 LETTERED BY *Robinson*
 CHECKED BY *R. L. F. T.*

CITY OF BALTIMORE
 DEPARTMENT OF PUBLIC WORKS
 BUREAU OF PLANS & SURVEYS
 PROPERTY LOCATION DIVISION
 WARD 11 SECTION 1
 BLOCK 484
 SCALE 1"=50' DATE May 1922

GIS data Courtesy of
the City of Baltimore, MOIT/EGIS





B-1572

1212 ST. PAUL